



OFFICE OF THE PURCHASING AGENT

TOWN OF ARLINGTON
730 Massachusetts Avenue
Arlington, MA 02476

Telephone (781) 316-3003
Fax (781) 316-3019

DATE: September 26, 2013

TO ALL BIDDERS

BID NO. 13-23

SUBJECT: Rehabilitation of Water Mains/Various Locations

ADDENDUM NO. 1

TO WHOM IT MAY CONCERN:

With reference to the bid request relative to the above subject, please note the following:

SEE ATTACHED

BIDDER MUST ACKNOWLEDGE ADDENDUM WITH SUBMISSION

All other terms, conditions and specifications remain unchanged.

Very truly yours,

Town of Arlington

Domenic R. Lanzillotti
Purchasing Officer

Based on comments and questions raised at the Pre-Bid Meeting held September 25, 2013, please distribute the following responses to all known plan-holders of Bid 13-23: Water Main Rehabilitation/Various Locations:

- Please replace Bid Sheet 1, Bid Sheet 2, & Bid Sheet 3 with the attached, revised Bid Sheets.
- Per the Town of Arlington Police Department, work hour restrictions (9:00 AM - 3:00 PM) will be enacted for any work on Summer Street, Medford Street, and Mystic Street.
- The contractor will be responsible for the coordination and acquisition of any staging/equipment storage areas that may be required for completion of the work.
- Per *Section VIII: Removal of Underground Non-Friable Asbestos Cement Pipe*, the removal, transportation, and proper disposal of Transite/AC Pipe shall be the sole responsibility of the contractor. This work will be paid as Item #11.
- Please refer to *Section VI, Item M: Existing Structures, Pipes, Conduits, Etc.* regarding the potential damage to existing sewer service laterals.
- Limited on-site parking for equipment and trucks will be allowed pursuant conditions and approval by the Town of Arlington Police Department.
- In accordance with *Section XVII: Bituminous Concrete Paving and Concrete Walks*, Permanent Trench Patching will be required after Town acceptance of the Temporary Patching. This is typically 60-90 days after completion of the project. Due to heavy traffic patterns, special attention should be paid to Temporary Patching on Summer Street, Medford Street, & Mystic Street.
- There shall be no additional compensation for time lost due to inability or difficulty to get a shutdown on the existing water system.

Bid Sheet 1 - King Street & Summer Street Area

ITEM #	QTY.	UNIT	DESCRIPTION	UNIT PRICE	AMOUNT
1	0	L.S.	FURNISH & INSTALL & REMOVE TEMPORARY BYPASS WATER LINES & SERVICE		
2	100	L.F.	FURNISH & INSTALL 8" CEMENT LINED DUCTILE IRON PIPE & FITTINGS.		
4	3	EA.	FURNISH & INSTALL 8" GATE VALVE & GATE VALVE BOX		
6	0	EA.	FURNISH & INSTALL 6" HYDRANT GATE VALVE & GATE VALVE BOX		
7	0	EA.	REMOVE EXISTING HYDRANT, FURNISH & INSTALL NEW HYDRANT & 6" HYDRANT BRANCH		
8	3	EA.	FURNISH & SET 3/4" CORPORATION COCK		
9	400	L.F.	FURNISH & INSTALL 3/4" COPPER SERVICE PIPE & FITTINGS		
10	3	EA.	FURNISH & SET 3/4" CURB STOP & BOX		
11	25	L.F.	REMOVAL, DISPOSAL, & HANDLING OF 8" TRANSITE PIPE		
12	60	C.Y.	TRENCH ROCK EXCAVATION		
13	75	C.Y.	UNSUITABLE TRENCH MATERIAL		
14	10	C.Y.	MISC. TRENCH EXCAVATION		
KING STREET & SUMMER STREET AREA TOTAL:					

Bid Sheet 2 - Mt. Pleasant Cemetery Area

ITEM #	QTY.	UNIT	DESCRIPTION	UNIT PRICE	AMOUNT
1	1	L.S.	FURNISH & INSTALL & REMOVE TEMPORARY BYPASS, WATER LINES & SERVICE (Medford Street Side Only)		
2	1,600	L.F.	FURNISH & INSTALL 8" CEMENT LINED DUCTILE IRON PIPE & FITTINGS.		
4	8	EA.	FURNISH & INSTALL 8" GATE VALVE & GATE VALVE BOX		
6	2	EA.	FURNISH & INSTALL 6" HYDRANT GATE VALVE & GATE VALVE BOX		
7	2	EA.	REMOVE EXISTING HYDRANT, FURNISH & INSTALL NEW HYDRANT & 6" HYDRANT BRANCH		
8	1	EA.	FURNISH & SET 3/4" CORPORATION COCK		
9	225	L.F.	FURNISH & INSTALL 3/4" COPPER SERVICE PIPE & FITTINGS		
10	1	EA.	FURNISH & SET 3/4 " CURB STOP & BOX		
11	50	L.F.	REMOVAL DISPOSAL & HANDLING OF 8" TRANSITE PIPE		
12	50	C.Y.	TRENCH ROCK EXCAVATION		
13	900	C.Y.	UNSUITABLE TRENCH MATERIAL		
14	50	C.Y.	MISC. TRENCH EXCAVATION		
MT PLEASANT CEMETERY AREA TOTAL:					

Bid Sheet 3 - Overlook Road & Ronald Road Area

ITEM #	QTY.	UNIT	DESCRIPTION	UNIT PRICE	AMOUNT
1	1	L.S.	FURNISH & INSTALL & REMOVE TEMPORARY BYPASS, WATER LINES & SERVICE		
2	2,525	L.F.	FURNISH & INSTALL 8" CEMENT LINED DUCTILE IRON PIPE & FITTINGS.		
4	11	EA.	FURNISH & INSTALL 8" GATE VALVE & GATE VALVE BOX		
6	5	EA.	FURNISH & INSTALL 6" HYDRANT GATE VALVE & GATE VALVE BOX		
7	5	EA.	REMOVE EXISTING HYDRANT, FURNISH & INSTALL NEW HYDRANT & 6" HYDRANT BRANCH		
8	80	EA.	FURNISH & SET 3/4" CORPORATION COCK		
9	2,000	L.F.	FURNISH & INSTALL 3/4" COPPER SERVICE PIPE & FITTINGS		
10	80	EA.	FURNISH & SET 3/4 " CURB STOP & BOX		
11	100	L.F.	REMOVAL, DISPOSAL, & HANDLING OF 8" TRANSITE PIPE		
12	950	C.Y.	TRENCH ROCK EXCAVATION		
13	1,870	C.Y.	UNSUITABLE TRENCH MATERIAL		
14	100	C.Y.	MISC. TRENCH EXCAVATION		
OVERLOOK ROAD & RONALD ROAD TOTAL:					